



LSP 4014

SPECIFICATIONS

DESCRIPTION
MODEL - LSP 4014
GVWR - 14,000 lbs.
Over All Length - approx. 45 ft.
Over All Width - 102 in.
Stick Pipe Capacity - 40 ft.
Empty Weight - 3,920 lbs.
RUNNING GEAR
Axle - 7,000 lbs.
Brakes - Electric
Tires - 235/80R16 LRE
Wheels - 16 x 6 8 Bolt Silver mod
FRAME
Main Frame - 12 in. Channel
Cross members - 6 in. Channel
Fenders - 10 in. Junior Channel
Bumper - 4 x 10 in Rectangular tube
A Frame Tongue - 6 in. Channel
Uprights - 1 1/2 Cold Rolled round
Hardware - Weld on winch with 30' tie down strap
BOLSTERS
Material - 3 x 5 Rectangular tube
ELECTRICAL
Plug - 7 RV molded plug
Wiring - Enclosed in conduit w/ junction boxes - connections soldered & shrink wrapped
Lights - Standard LED package
SAFETY
Chains - Rated to match
Break Away - Battery, battery box, and switch
Decals - Warning decals & reflective tape
ACCESSORIES
Jack - 12K Side wind drop leg jack
Roller System - 8) 10 in. rubber rollers
FINISH
PPG Paint - Industrial urethane- White, Black, Orange, Yel.

